BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2014-15/BD/WORK_INDENT13907

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/07/2014-15, Date: 31.10.2014

construction of class rooms at Ramachandrapura in ward no. 10 (Doddabommasandra), Vidyaraynapura sub division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of KRISHNA REDDY	
				In Figures	In Words
1	83.68	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work.	Sqm	240.0	Rupees Two Hundred Forty Only
2	4.5	Providing and removing centering, shuttering, strutting, propping etc., for chajjas, corbels etc., including edges including cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work.	Sqm	260.0	Rupees Two Hundred Sixty Only
3	263.18	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work.	Sqm	300.0	Rupees Three Hundred Only
4	45.48	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878cum and fine aggregates @ 0.459 cum wuth superplastisier @ 3lts confirming to IS 9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, wall (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work.	Cum	5780.0	Rupees Five Thousand Seven Hundred Eighty Only
5	8.73	Providing and laying in position reinforced cement concrete ofmix M20 with OPC cement @ 24kgs, with 12 mm and down size graded granite metal coarse aggregates @ 0.5175 cum and fine aggregates @ 0.345 cum with superplastisiser @ 0.225lts,machine mixed, well compacted for plain chajja of 7.5 cms. average thickness, upto ground floor lever, including cost of all materials, labour, HOM of machinery, curing, etc complete as per specifications and directions of engineer in charge of the work.	Sqm	450.0	Rupees Four Hundred Fifty Only
6	57.73	Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery etc complete as per specifications and directions of engineer in charge of the work.	Qtl	7400.0	Rupees Seven Thousand Four Hundred Only

Executive Engineer
Byatarayanapura Division
Yelahanka [illegible], B.B.M.P.
Bangalore - 560 092

7	72.96	Providing and constructing burnt brick masonry with approved quality of modular bricks of standard size of class designation 50 (table moulded) with cement mortar 1:6 for basement and superstructure including cost of materials, labour charges, scaffolding, curing etc complete as per specifications and directions of engineer in charge of the work.	Cum	6000.0	Rupees Six Thousand Only
8	142.31	Providing and laying integral cement based waterproofing treatment including preparation of surface as required for treatment of roofs, balconies, terraces etc, consisting of following application. (a) Applying and grouting a slurry coat of neat cement using 2.75kg/sqm conforming admixed with proprietary water proofing compound conforming to IS:2645 over the RCC slab after cleaning the surface before treatment, (b) laying cement concrete using broken brick bats 25mm to 100mm size with 50% of cement mortar 1:5 admixed with proprietary water proofing compound conforming IS:2645 over 20mm thick layer of cement layer of cement mortar 1:5 admixed with proprietary water proofing compound to required slope and treating similarly the adjoining walls upto 300mm height including rounding off junction of walls and slabs, (c) after two days of proper curing, applying a second coat of cement lurry admixed with proprietary water proofing compound (d) Finishing the surface with 20mm thick jointless cement mortar of mix 1:4 admixed with proprietary water proofing compound and finally finishing the surface with trowel and neat cement	Sqm	800.0	Rupees Eight Hundred Only
9	145.97	Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to ceiling including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work.	Sqm	200.0	Rupees Two Hundred Only
10	292.17	Providing 20mm thick cement plaster in single coat with cement mortar 1:4, to stone masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work. (Inside wall)	Sqm	220.0	Rupees Two Hundred Twenty Only
11	438.14	Providing lime rendering for plastering to wall and ceiling, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work.	Sqm	28.0	Rupees Twenty Eight Only
12	163.87	Providing 18mm thick cement plaster in single coat with cement mortar 1:6, to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work. (Out side Wall)	Sqm	180.0	Rupees One Hundred Eighty Only
13	0.68	Providing Honne wood frames of doors, windows, clerestory windows, ventilators, and other frames, wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries etc complete as per specifications and directions of engineer in charge of the work.	Cum	110000.0	Rupees One Hundred Ten Thousand Only

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

14	2	Fixing of door frame in an existing opening including embedding Nos 458.43 frame in floor and walls after cutting masonry for holdfasts for embedding holdfast in cement concrete 1:3:6 of 20 mm and down size granite metal painting two coats of coal tar to sides of frame, making good the damages to walls and floor as required and disposal of the debries with lead upto 50 m. including cost of materials, labour charges, etc complete as per specifications and directions of engineer in charge of the work.	Nos	1100.0	Rupees One Thousand One Hundred Only
15	4.41	Providing and fixing in position fully panelled Honne wood shutters for doors, styles and rails of 40mm. thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries complete as per specifications. (excluding cost of fixtures). etc complete as per specifications and directions of engineer in charge of the work.	Sqm	4800.0	Rupees Four Thousand Eight Hundred Only
16	12.96	Providing and fixing in position Honne wood half panelled shutters at bottom and half glazed at top for windows shutters with styles and rails of 35mm. thick, 75mm wide in two halves with panels of 25mm thick 3mm thick reeded glass for top panels fixed with wooden beading including cost of materials, labour charges, HOM of machineries complete as per specification (excluding cost of fixtures) Specification No Providing an fixing in position teak wood half paneled shutters at bottom and half glazed at top for window sutters with styles and rails of 35mm, thick, 75mm wide in two halves with panels of 25mm thick, 3mm thick reeded glass for top panels fixed with wooden beading including cost of materials, labour charges, HOM of machineries complete as per specifications. (Excluding cost of fixtures) etc complete as per specifications and directions of engineer in charge of the work.	Sqm	4500.0	Rupees Four Thousand Five Hundred Only
17	194.4	MS Bars at 0.62Kg/Mtr = 194.40 x 0.62 = 120.53 Kgs etc complete as per specifications and directions of engineer in charge of the work.	Sqm	42.0	Rupees Forty Two Only
18	6.86	Providing wall black boards in CM 1:3 two coats of black paint including finishing etc complete as per specifications and directions of engineer in charge of the work.	Sqm	850.0	Rupees Eight Hundred Fifty Only
19	23.54	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work.	Cum	4500.0	Rupees Four Thousand Five Hundred Only
20	127.76	Flooring with 25mm to 40mm thick polished Thandur blue stone slabs using cement mortar 1:6, 25mm thick over existing cement concrete bed or top roof laid to line and level and jointed with cement slurry mixed with pigment to match the shade of the slab, including cost of materials, labour, curing, polishing etc complete as per specifications and directions of engineer in charge of the work.	Sqm	1200.0	Rupees One Thousand Two Hundred Only

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

21	438.14	Providing and applying two coats with oil bound washable distemper of approved brand and shade on wall surface including priming coat with distemper primer after thoroughly brooming the surface free from mortar drops and other foregin matter including preparing the surface even and sand paper smooth, cost of materials, labours, etc complete as per specifications and directions of engineer in charge of the work.	Sqm	65.0	Rupees Sixty Five Only
22	163.87	Providing and finishing external walls in tow coats with water proof cement paint of approve brand and shade to give an even shade after thourghly brooming the surface to remove all dirt and losse powdered material, free from mortar dops and other foreign matter cost of materials, labours, etc complete as per specifications and directions of engineer in charge of the work.	Cum	80.0	Rupees Eighty Only
23	34.74	Providing and applying painting two coats (excluding priming coat) on new wood surface and / or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labour, etc complete as per specifications and directions of engineer in charge of the work.	Sqm	85.0	Rupees Eighty Five Only
24	10.2	Providing lath plaster with cement mortar 1:3 5cms thick with 6mm dia mild steel bars at 20 cms c to c both horizontally and vertically fixing chicken mesh for drop chajja, facia, backing to cup boards including cost of all materials, labour, providing and removing form work HOM of machineries, curing, etc complete as per specifications and directions of engineer in charge of the work.	Sqm	1100.0	Rupees One Thousand One Hundred Only
25	6.3	Providing & fixing factory made PVC Door frame of size 50x47 mm with a wall thickness of 5mm, made out of extruded 7mm rigid PVC foam sheet metered cut at corners & jointed 2No.s of 150mm long brackets of 15x15 mm M.S. Square tube of 19 gauge. The door frame to be fixed to the wall using M.S. Screws of 65/80mm size complete as per manufactures specification & direction of Engineer-in charge SOLID PVC DOOR FRAME etc complete as per specifications and directions of engineer in charge of the work.	Sqm	600.0	Rupees Six Hundred Only
26	6.3	Providing & fixing 30mm thick factory made rigid foam prelam panelled Door Shutters made from M.S. tube of 19x19mm, 19 gauge for styles and 15x15mm for top & bottom rails, covered with heat moulded prelaminated PVC 'C' Channel of 5mm thick sheet & 30x50mm wide of form styles & 5mm thick & 75mm wide prelaminated PVC sheets for top rail, lock rail & bottom rail on either side & 5mm thick, 20mm wide cross PVC sheet as gap insert for top rail & bottom rail, Panelling of 5mm thick PVC sheet Prelaminated on either side fitted in the M.S. frame, sealed to the styles &rails with PVC designer beading on either side & joined together with solvent cement adhesive etc., complete as per manufactures specification & direction of Engineer –in-charge fixed to frames with 3nos of 75mm. Aluminium hinges. SOLID PANEL PRELAM PVC DOOR SHUTTER etc complete as per specifications and directions of engineer in charge of the work.	Sqm	4300.0	Rupees Four Thousand Three Hundred Only

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

27	6	KSRB 7.10 : Providing and fixing in position anodized aluminium windows and ventilators as per approved drawings with sliding shutters using double track window frame section of size 61.85x31.75mm. with 1.2mm thick bottom section weight 0.695 Kg/m, sides and top sections 1.3 mm. thick weight 0.659 kg/m; and shutter comprising top and bottom section of size 40mmx18mm, 1.25mm thick 0.417 kg/m, shutter outer side 40mmx18mm, 1.25mm, thick, weight 0.417 kg/m, shutter interlock section 40mmx26.7mm, 1.1mm thick, weight 0.469 kg/m the shutters mounted on nylon rollers with approved quality of fixtures such as aluminium handles tower bolts etc ; and providing and fixing 5.5mm, thick plain glass for shutters fitted with rubber beading aluminium section anodised 12 to 15 microns, including cutting to required length, joints mitred subdividing the frame tenonned and riveted in the assembled frame stiffened with end clops at corners angles etc., and fixed to the walls, lintels, floor beams/cills as the case may be with necessary steel screws, raul plugs, or teak wood gatties including cutting masonry or concrete and making good the original surface using cement mortar,	Sqm	3900.0	Rupees Three Thousand Nine Hundred Only
28	21.6	Providing white glazed tiles of size 10mm thick for flooring, treads of steps and landing, laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing using white cement with matching colour pigment, including cost of materials, labour, etc complete as per specifications and directions of engineer in charge of the work.	Sqm	900.0	Rupees Nine Hundred Only
29	120	Groove Cutting : Supplying ... dia 2mm/2.5mm thick heavy gauage PVC Conduit Pipe with bends metal junction boxes adhesive paste etc., and bracing U or J hooks and cement plastering up to the surface of the brick level and run with 18 SWG GI fish wire run through out the conduit wherever necessary 32 mm dia 2.5mm thick etc complete as per specifications and directions of engineer in charge of the work.	Mtrs	72.0	Rupees Seventy Two Only
30	3	Supplying and flush mounting teak wooden box with out front plank made of not less than 12mm thick wood after due groove cutting necessary masonry patch work 10"X7"X3" (300X228X76mm) etc complete as per specifications and directions of engineer in charge of the work.	Each	72.0	Rupees Seventy Two Only
31	4	8"X6"X3" (300X228X76mm)	Each	60.0	Rupees Sixty Only
32	25	Supplying and fixing PVC/metal conduit accessories special type Junction Box 32 mm Junction Box (I. 5/P. 3) etc complete as per specifications and directions of engineer in charge of the work.	Each	32.0	Rupees Thirty Two Only
33	8	Deep 32 mm Junction Box	Each	35.0	Rupees Thirty Five Only
34	8	Fan Box 18 /SWG	Each	60.0	Rupees Sixty Only
35	5	Point Wiring using copper wire with switch Supplying and wiring adopting loop system in existing PVC Conduit / casing caping using Copper PVC insulated multi strand 2x1.5 Sqmm copper wire with a 6 Amps flush type SP control switch shall be fixed on the existing plastic sheet gang box the other end of the wires shall be terminated with sufficient loose length in a wood PVC round block complete for each outlet Point Wiring using Class A Materials a) Short point upto 3Mtr from tapping point to out let via switch etc complete as per specifications and directions of engineer in charge of the work.	Each	180.0	Rupees One Hundred Eighty Only
36	5	b) Medium point above 3mtr upto 6mtr from tapping point to out let via switch	Each	290.0	Rupees Two Hundred Ninety Only

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

37	4	C) Long point above 6mtrs upto 10mtrs from tapping point to outlet via switch	Each	400.0	Rupees Four Hundred Only
38	2	Supplying and fixing superior quality modula switch mounting polyorbonate plate with ncecessary supporting back plate with required nos. of machines screwes, bolts nuts etc., complete on the existing metal/PVC box 1 to 3 Modular etc complete as per specifications and directions of engineer in charge of the work.	Each	90.0	Rupees Ninety Only
39	2	8 Modular	Each	190.0	Rupees One Hundred Ninety Only
40	25	Supplying and fixing of modular switch / socket/Stepped electrical fan regulator / dimmer / telephone socket etc on existing modular switch plate 6Amps one way. etc complete as per specifications and directions of engineer in charge of the work.	Each	110.0	Rupees One Hundred Ten Only
41	6	6Amps 3way Socket.	Each	175.0	Rupees One Hundred Seventy Five Only
42	4	Stepped Fan Regulator	Each	550.0	Rupees Five Hundred Fifty Only
43	8	Supply patty type fluorescent tube light fitting of 4' - 36/40 watts fluorescent tube fitting, made out of M.S. Sheet and stove enameled with low loss open construction copper wound ferromagnetic ballast, starter, locking, locking type brass contact holder mounted on double fold type sheet base fully wired for used on 230 Volts A C Supply including fluouresecent tube Group 'A' etc complete as per specifications and directions of engineer in charge of the work.	Each	420.0	Rupees Four Hundred Twenty Only
44	5	Supplying of Incandescent lamps B.C. 100Watts etc complete as per specifications and directions of engineer in charge of the work.	Each	15.0	Rupees Fifteen Only
45	4	Supplying capacitor type ceiling fan complete with down rod blades, shackle, canopies etc., for operation on 230 volts, 50 cycles. Single phase AC supply conforming to ISS-374-1979 and with double ball bearing system Regulator Model (Khaitan, Crompton Geaves, Orient, Polar, Bajaj, Usha, Havells, Almonard 56" Sweep (1400 mm) etc complete as per specifications and directions of engineer in charge of the work.	Each	2100.0	Rupees Two Thousand One Hundred Only
46	1	Supplying and fixing 32Amps security and energy savings DP switch with key tag suitable to operate on 230 Volts 50Hz AC supply & completely wired on existing box Group A etc complete as per specifications and directions of engineer in charge of the work.	Each	650.0	Rupees Six Hundred Fifty Only
47	1	Supplying an fixing one of 230 volts PBBC bakelite staight or slant batten holder and wiring with in 60w/230 Volts lamps etc complete as per specifications and directions of engineer in charge of the work.	No	70.0	Rupees Seventy Only
48	1	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and wiring complete as required 5-32 Amps etc complete as per specifications and directions of engineer in charge of the work.	Each	600.0	Rupees Six Hundred Only
49	1	Supply and fixing polished wood board made of not less than 15mm thick plank on both sides with planks made out of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws 20"x20"x2.5" etc complete as per specifications and directions of engineer in charge of the work.	Each	300.0	Rupees Three Hundred Only
50	1	Supplying and fixing of porcelain fuse channel with cut out on existing wooden /panel using necessary nuts, bolts and washers 32 Amps etc complete as per specifications and directions of engineer in charge of the work.	Each	110.0	Rupees One Hundred Ten Only

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

51	1	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C cutouts and other equipment on the meter board using 40mm dia 2.90 thick GI pipe 2.5 mtr long buried in a pit.. The pit should be filled with equal proprotion of salt and charcol 150mm alround the pipe to complete depth. The connection from the pipe to the conduit etc, is to be established through GI wire of size as oer ISI specification 7.3.3 of Is 732 using 12mm dia nuts, washers and checknuts etc the pipe shall have 16 through holes of 122 mm dia etc complete as per specifications and directions of engineer in charge of the work.	Each	2200.0	Rupees Two Thousand Two Hundred Only
52	20	INSULATED CABLE ON MESSENGER WIRE Using 2 single core wires for a single phas and 4 single core wies for 3 phase supplying and stringing PVC insulated and PVC sheathed 650/1100V class aluminium conductor of size supported by 3.15mm (10 SWG) GI messenger wire with two breaks insulators, one at each end of the span wit suspenders at intervals of 0.75m. Each suspender shall be of porcelain reel insulator of suitable core through which insulated wire passes (single core or twin core as the case may be) and this reel insulator shall be fixed to the messanger wire using 2mm (No. 14SWG) GI wire suitably bent and twisted. Separate reel insulated shall be provided for each wire the messanger wire shall be bed-ended on the clamp provided to the departmental pole wide c) 6 Sqmm item No. 4 above etc complete as per specifications and directions of engineer in charge of the work.	Mtr	55.0	Rupees Fifty Five Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92